

Container House Installation Guide

A web-light installation workflow for buyer review before confirming drawings and site conditions.



Step	Buyer / Installer check
1. Site preparation	Confirm foundation level, anchor position, drainage, lifting access and local safety requirements.
2. Unloading and frame positioning	Use suitable forklift or crane. Keep packed units stable and check frame corners before unfolding or assembly.
3. Main structure assembly	Install or unfold frame, roof, side walls and bottom frame according to project drawings.
4. Interior and utility connection	Install doors, windows, wall panels, floor, electrical lines, plumbing and optional sanitary module.
5. Final inspection	Check fasteners, waterproof seams, electrical protection, doors/windows, floor finish and packing list.

Before shipment, ask Yihong for the final installation video, drawings and packing list matched to your purchased model.

Source material reference: YH_ECH_INST_001_20260518.pdf and organized packing/loading media.